



- EROSION CONTROL NOTES:**
1. INSTALL SILT FENCE AND CONSTRUCTION ENTRANCE PRIOR TO START OF CONSTRUCTION.
 2. CONSTRUCTION ENTRANCE TO BE LOCATED IMMEDIATELY OFF OF 50TH STREET IN SAME LOCATION AS FINISHED DRIVEWAY.
 3. RESTORE ALL DISTURBED AREAS WITH 4" TOPSOIL AND SOD.
 4. NO CONSTRUCTION ACTIVITY ALLOWED BELOW ELEVATION 931.0.

- CONSTRUCTION NOTES:**
- [Solid Grey Box] = CONSTRUCT DRIVEWAY WITH:
 - 2" TYPE SP 12.5 BITUMINOUS WEARING COURSE MIXTURE (2,B)
 - BITUMINOUS TACK COAT
 - 2" TYPE SP 12.5 BITUMINOUS WEARING COURSE MIXTURE (2,B)
 - 6" CLASS 5 AGGREGATE BASE, 100% CRUSHED
 - 12" SELECT GRANULAR BORROW (MODIFIED)
 - PAID WITH UNIT PRICE BID ITEMS
 - [Dotted Box] = CONSTRUCT CONCRETE SIDEWALK WITH:
 - 5" CONCRETE
 - 4" SELECT GRANULAR BORROW (MODIFIED)
 - PAID WITH UNIT PRICE BID ITEMS
 - [Hatched Box] = CONSTRUCT CONCRETE SIDEWALK ON STOOP (REFER TO 3.XX SERIES DRAWINGS FOR ADDITIONAL INFORMATION) PAID UNDER BUILDING LUMP SUM BID ITEM
- CONCRETE SIDEWALK TO BE SLOPED 2% AWAY FROM THE BUILDING. EDGE OF SIDEWALK TO BE 6" ABOVE EDGE OF BITUMINOUS PAVEMENT.



HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DESIGNED: MRW
 DRAWN: MRW
 CHECKED: JRR

MICHAEL R. WARNER
 LIC. NO. 44693 DATE XX/XX/2013

BOLTON & MENK, INC.
 Consulting Engineers & Surveyors
 MANKATO, MN FAIRMONT, MN SLEEPY EYE, MN BURNSVILLE, MN
 WILLMAR, MN CHASKA, MN RAMSEY, MN MAPLEWOOD, MN
 BAXTER, MN ROCHESTER, MN AMES, IA SPENCER, IA

REV.	BY	DATE

LAKE ELMO, MINNESOTA
 PUMPHOUSE NO. 4
 SITE PLAN
 PROPOSED MODIFICATIONS