

**FRANK ZAMORA'S CONCRETE**

717 2nd St.

St. Paul Park, MN 55071

(651) 458-9461

naomi@frankzamorasconcrete.com



## ESTIMATE

**ADDRESS**

City of Lake Elmo

Attn: Rob Weldon

3800 Laverne Ave N

Lake Elmo, MN 55042

**ESTIMATE # 1525****DATE 07/26/2016**

ACTIVITY	QTY	RATE	AMOUNT
<b>Services</b>		9,800.00	9,800.00
Remove and replace 9' x 17' entry/sidewalk into city hall.			
Remove and replace 6' x 146' 3" sidewalk on the north and west side of city hall.			
Remove and replace 4' 4" x 9' section of sidewalk leading into police station.			
4 - 4 1/2in. concrete, deeper around the edges.			
Mix design: Xdrive FD 3/4 and 3/4 granite with field stone.			
3/8in. rebar for reinforcement, 3-4ft. on center.			
Class 5 or limestone base.			
Tool cuts for control joints.			
Light broom finish.			
Slope for proper drainage.			
Surface sealer applied when complete.			
Note:			
We recommend that you cure the concrete with water 3 days following the pour.			
References are available.			
Call if you have any questions.			
TOTAL			<b>\$9,800.00</b>

Accepted By

Accepted Date